

DWARF WALL MODULAR SYSTEM

When purchasing the dwarf wall modular system, the following components are included:

- 1) Perimeter foundation with ground anchors
- 2) 18 x 4 steel profiles and mounting brackets
- 3) Shaped and pre-drilled grey concrete fiber boards + screws, nuts and bolts

The concrete fiber boards in the modular system can be left untreated or you can coat them in paint, clad with wood or a brick effect. Coatings not included.



1) The perimeter foundation is positioned, leveled and concreted into position.



2) The profiles are then positioned on the perimeter foundation and the modular system is assembled from there.



3) The cement fiber boards are attached with screws to the interior and exterior profile frames.



The greenhouse is then assembled on the dwarf wall.

DWARF WALL MODULAR SYSTEM

